UNIVERSITY OF ALLAHABAD

QUOTATION NOTICE

QUOTATION NOTICE NO. AU/UE-09-(C)/2026-27 **Date:** 19.11.2026

Sealed quotations are invited from experienced Civil Contractor/Firms having valid GSTN and PAN Number. Quotation can be seen and downloaded from **www.allduniv.ac.in**, **& www. eprocure.gov.in**. After filling of the quotation the bidder will submit the quotations in a sealed envelope either through registered post or courier to Purchase Officer, Purchase & Store Department, First Floor, Dean CDC, Senate Campus as per time schedule. The bidder will explicitly mark the Quotation Notice Number, Name of Work on the envelope.

Detailed below:

Name of Work:- Repairing/plastering, painting, P/L floor tile etc. at Room No. B-101 Department of Physics, Faculty of Science, University of Allahabad, Prayagraj.

Estimated Cost: - Rs. 48, 175/-

Time of Completion of work: 30 Days.

Date of downloading of quotation: From: 19.11.2026 to: 09.12.2026

Date of submission of quotation:	Up to 10.12.2026 at 4:30 P.M.
Date of opening of quotation:	on 11.12.2026 at 11:00 A.M.

Venue of Opening of Quotation: Office of the Chairperson, Central Purchase Committee, University of Allahabad, Prayagraj.

University Engineer
University of Allahabad

CC to:-

1 The Chairman, Central Purchase Committee for kind information.
2 Purchase Officer for kind information.
3 Finance Officer for kind information.
4 Notice Board, office of the University Engineer.

University Engineer

University of Allahabad

To, Date:-

M/s .....
.....
.....

Name of Work: Repairing/plastering, painting, P/L floor tile etc. at Room No. B-101 Department of Physics, Faculty of Science, University of Allahabad, Prayagraj.

Dear Sir,

Please quote your rates as per attached bill of quantity. Your quotation should reach to the office of the Purchase Officer, Dean CDC Office, First floor, Senate Campus latest by 10.12.2026 up to 4:30 P.M. either through registered post or through courier. Quotation will be opened at 11:00 A.M. on the 11.12.2026/or as per suitable date of Purchase Office in the presence of desirous bidders.

Terms and Conditions:

1. Unsealed & conditional quotations shall not be accepted.
2. University reserves right to reject or accept any or all the quotation without assigning any reason thereof or distribute the whole work between two or more contractors/firms.
3. Rates shall be valid for (30) thirty days from the date of opening of quotations.
4. Taxes shall be deducted as per rules.
5. Your rates should be inclusive of all taxes.
6. The payment of wages/ allowance and other benefits admissible to persons employed by the contractor for the job shall be the sole responsibility of the contractor as their employer under law.
7. The contractor shall be legally liable and responsible for any contravention of any legal requirement and consequent liability with regard to persons deployed by him in connection with the work assigned to him by the University.
8. In case of any dispute the decision of the Vice-Chancellor shall be final and binding on both the parties.
9. All the litigations will be subject to the jurisdiction of courts at Allahabad.
10. In case the work is not completed in stipulated time penalty of 5% of the value of work will be deducted from the contractors bill subject to maximum of 10% of total amount of bill.
11. Statutory deductions as per rule will be made from the bill.

Signature of Contractor
With Seal

University Engineer
University of Allahabad

BILL OF QUANTITY

NAME OF WORK: Repairing/plastering, painting, P/L floor tile etc. at Room No. B-101 Department of Physics, Faculty of Science, University of Allahabad, Prayagraj.

Sl. No.	Description	Quantity	Unit	Rate (Rs.)	Amount (Rs.)
1	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) size of tile 600x600mm. Code/DSR/2018/11.41.2	17.00	Sqm		
2	12mm cement plaster of mix 1:4 (1 cement: 4 coarse sand). Code/DSR/2018/13.4.1	14.00	Sqm		
3	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 meters lead. Code/DSR/2018/15.56	15.00	Sqm		
4	Distempering with Ist quality acrylic distemper, having VOC (Volatile Organic Compound) Two Coats. Code/DSR/2018/13.90.1	65.00	Sqm		
5	Providing and fixing wash basin with C.I. brackets, 15mm C.P. brass pillar taps. Code/DSR/2018/17.7.2	1.00	Nos		
6	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade: one or more coats on old work. Code/DSR/2018/13.99.1	18.00	Sqm		
7	P/A white cement based putty of average thickness 1mm. Code/DSR/2018/13.80	60.00	Sqm		
8	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply. Code/DSR/2018/18.7.2	1.00	Mtr		
9	Providing and fixing P.V.C. waste pipe for sink or wash basin including P.V.C. waste fittings complete. Code/DSR/2018/17.28.2.2	1.00	Nos		
10	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with float glass panes of 4.0mm thickness. Code/DSR/2018/21.3.1	2.00	Sqm		
11	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. Code/DSR/2018/13.88	65.00	Sqm		
12	Providing and fixing unplasticised PVC connection pipe with brass unions. Code/DSR/2018/18.21.2.2	1.00	Nos		
13	Providing and fixing PTMT angle stop cock 15mm nominal bore, weighing not less than 85gms. Code/DSR/2018/18.63	1.00	Nos		
				Total=	

Your rates should be inclusive of all taxes.

Signature and Address of Contractor

University Engineer
University of Allahabad